Order #: # Thinksign NOTES: 1.DISPLAY IS REAR VENTILATED, DO NOT BLOCK UP VENTILATORS. 2.FRONT ACCESS FOR SERVICE. Xtreme-10 96x320-SMD 3 In 1 3.THINKSIGN IS NOT RESPONSIBLE FOR THE MAIN ELECTRICAL DISCONNECT. Support@thinksign.com 4.THINKSIGN IS NOT RESPONSIBLE FOR THE MOUNTING HARDWARE OR THE INTEGRITY OF THE STRUCTURE THE DISPLAY IS MOUNTED TO. 120V / 2746W / 23A / 422LBS / Per Face www.ThinkSign.com Please Keep For Service! Follow air flow instructors or sign will be damaged 8¹³/_{16"} [223.50] AIRFLOW Open the cabinet Slave Side 10'-6" [3200.00] 4³/4" [120.00] Hole for 3'-0¹/4" [920.00] 5'-1⁷/16" [1560.00] DETAIL A SEE DETAIL A Master Slave mounted up right 0 000 0 0 000 0 Temperature Brightness HUB HUB HUB Sensor Must be mounted up right

120V 23A

□ 120V 23A

NET CABLE 5E



Installing & Replacing the Wireless Package

The ThinkSign LED displays that are ordered with the wireless package are shipped pre-configured. The radios are meant to be plug-and-play, with little to no IT experience needed.

The Sender

- Plug a cable into the LAN port of the sender.
- Plug the POE unit power into the wall and plug the cable from the sending unit into the "POE" port.
- Plug a cable from the LAN port of the POE to an open port on your router or switch.
- Mount the sending unit and turn on the sign.
- After 2-3 minutes, the radios should sync up and you should be able to connect to your sign successfully after installing the Smart LED Manager Pro software.







The Receiver

- The receiver is configured and shipped with the unit and plugged into the master side of the sign.
- Plug in the cable marked "Wi-Fi" into the LAN port of the receiver.
- Next, mount the receiver vertically on an external area of the sign/pole facing the direction of the site the sender will be installed.





Wifi Communication Setup



Click on the sync button on the software homepage.

Next, click on the

Connection Guide

